
R ZIIG

TECHNICKÝ A ZKUŠEBNÍ ÚSTAV STAVEBNÍ PRAHA, s.p.

Technical and Test Institute for Construction Prague

Akreditovaná zkušební laboratoř, Autorizovaná osoba, Notifikovaná osoba, Oznámený subjekt, Subjekt pro technické posuzování, Certifikační orgán, Inspekční orgán / Accredited Testing Laboratory, Authorised Body, Notified Body, Technical Assessment Body, Certification Body, Inspection Body. Prosecká 811/76a, 190 00 Praha 9





tel.: +420 387 023 211, e-mail: pilarova@tzus.cz, www.tzus.eu



TEST REPORT

issued by Testing Laboratory No. 1018.3 accredited pursuant to ČSN EN ISO/IEC 17025:2018 by Czech Accreditation Institute

No. 020-049509

on test of - water vapour permeability

- water penetration rate

- bond strength

- bridging of cracks

Customer:

Naici Italia srl

Address:

Via Chiavari 35, 00048 Nettuno (Roma), Italia

Company ID:

IT 02815240599

Plant:

Via Chiavari 35, 00048 Nettuno (Roma), Italia

Test sample:

NAILASTIC BIT

Order No.:

Z020230398

Number of pages of the Test Report incl. title page: 3

Pages of Annexes: -

Prepared by:

Ing. Dana Pilařová

specialist

Approved by:

THUSEBNI USTAV STALL THUSEBNI I Abording to 1018 Stall TRAHAM TO STALL THUSEBNI I ABORDING TO 1018 STALL THUSEBNI I ABORDING TO 1018 STALL THUSEBNI I ABORDING TO 1018 STALL THUSEBNI I ABORDING THUSEBNI I ABORDING THE STALL THUSEBNI I ABORDING THE

Ing. Vilém MgI manager of the testing department

Print No.: 1

Number of prints: 2

České Budějovice, on 29.1.2024

razitko zkušebni laboratoře č. 1018.3

Declaration: 1) The test results in this Report relate only to the tested article and they do not substitute any other documents
2) The Test Report must be copied as a whole only otherwise a written consent of the testing laboratory is needed.

Technical and Test Institute for Construction Prague, Central laboratory

Nemanická 441, 370 00 České Budějovice, Czech Republic

Bank: Komerční banka, Praha 1

Phone.: +420 495 500 930

Account No.: 1501-931/0100

www.tzus.eu e-mail: pilarova@tzus.cz

Entered in the Commercial Register maintained by Municipal Court in Preque, Section ALX, Insert 711, Comp. ID: 00015679, VAT: CZ00015679

1. Sample data

Sample:

NAILASTIC BIT

Evidence Number:

VZ020234778

Order:

date 26.10.2023

Date of sample delivery:

27.10.2023

Sampling method

original intact packaging

Method of the sample preparation:

1. layer NAILASTIC BIT + 5% water, TEX-CORE 130, NAILASTIC BIT

(undiluted), technological pause 5 hours

2. layer NAILASTIC BIT (undiluted), technological pause 16 hours

3. layer NAILASTIC BIT (undiluted)

Samples were deposited 28 days in air-conditioned climate with 23°C

and 50 % rel. humidity.

Thickness of layer after drying: 1.2 mm

Data of sampling conditions, plan and sampling procedure, if necessary, the name of the person performing the sampling are listed in the minutes of sampling, which is stored in the testing department.

The results apply to the sample as received.

2. Test methods

Identification of the t	est method	Title of the test method
ČSN EN 1542	Products and system for the protection and repair of concrete structures - Test methods - Measurement of bond strength by pull-off	Measurement of bond strength by pull-off
ČSN EN ISO 7783	Paints and varnishes - Determination of water-vapour transmission properties - Cup method	Determination of water vapour transmission rate
ČSN EN 1062-3	Paints and varnishes - Coating materials and coating systems for exterior masonry and cocrete - Part 3: Determination and classification of liquid-water transmission rate (permeability).	Determination of water permeability
ČSN EN 14891, method A.8	Liquid-applied water impermeable products for use beneath ceramic tiling bonded with adhesives - Requirements, test methods, evaluation of conformity, classification and designation	Determination of the crack bridging

Deviations from a standard procedure or the use of non-standardized methods: were not applied.

3. Test results

The tests were carried out on:

14.11. - 20.12,20223

The tests were performed by:

Ing. Dana Pilařová, Jan Lenc

Place of testing:

Testing Department České Budějovice

Date about person performing the test, testing equipment and about test conditions are listed in test minutes. All measurement and test equipment are calibrated according to valid plan of the testing department.



3.1 Determination of the bond strength by pull-off test acc. to EN 1542

Substrate	Bond strength [MPa]		Rupture typology
	particular values	0.8	100 % B (in the plaster)
		0.8	100 % B (in the plaster)
Concrete		8.0	100 % B (in the plaster)
(EN 1766)		0.7	100 % B (in the plaster)
(LIV 1700)		0.8	100 % B (in the plaster)
	average value	0.8	

3.2 Determination of the water penetration rate acc. to EN 1062-3

Substrate	Water penetration rate [kg/(m².h0.5)]	
	particular values	0.07
	·	0.05
Sand-lime brick		0.04
	average value	0.05

3.3 Determination of the water vapour permeability acc. to EN ISO 7783

The test on water vapour permeability was carried out on a plate of glass frit under conditions of 50 % RH, 23°C.

	Equivalent diffusion thickness s _d [m]	Water vapour permeability V [g/(m².24hrs)]
particular values	1.88 1.81	10.8 11.2
	1.75	11.7
average value	1.82	11.2

3.4 Determination of bridging of cracks acc. to EN 14891, A.8

	Value determined	
	partial	average
	16.25 mm	
23°C – elongation at the failure	15.84 mm	16.13 mm
	16.30 mm	
	4.63 mm	
-20°C – elongation at the failure	4.50 mm	4.53 mm
	4.47 mm	

END OF THE TEST REPORT

